



QUADRANT ROAD

DUKE STREET

- carefully remove existing timber door leaves and frames. new ppc framed clear glass fire doors with deadlock and push/ pull handles
- sounding board and pulpit removed. textured surface treatment behind
- new central projector and screen
- new removable lecturn and cabling
- new 'floating' platform, baptistry retained
- removed fixed seating make good cork floors with wood filler to ensure smooth solid substrate.
- apply floor sealer, tackifier and flotex carpet/ marmoleum tiles.
- add floor studs to row ends
- 257 SEATS
- carefully remove pigeon holes and relocate to suitable 'private' location
- carefully remove existing timber door leaves and frames. new ppc framed clear glass fire doors with deadlock, push/ pull handles and mag lock hold open linked to panic button from reception desk.

**PROPOSED PLAN**  
**SUNDAY 'CHAMFER'**  
**245 SEATS**  
**1:100@A3**